

EXHIBIT D**

Meets Buy America (*See Notes 2, 3, 4, 5)	Structure Type - (CSI Division)	BID ITEM DESCRIPTION	QUANTITY	UNIT
N/A	Bridge (03)	STRUCTURAL CONCRETE (BRIDGE)	6.5	CY
*	Bridge/Building (05)	REINFORCING STEEL, EPOXY COATED	1701	LB
*	Bridge/Building (05)	REINFORCING STEEL, STAINLESS STEEL	346	LB
*	Bridge/Building (05)	STRUCTURAL STEEL	4630	LB
*		BRIDGE DRAINAGE SYSTEM	1	LS
N/A	Bridge/Building	CONSTRUCTION SURVEY	1	LS
N/A	Bridge/ Building	MOBILIZATION	1	LS
*	Bridge (05)	FENCE, PERFORATED ALUMINUM	36	LF
*		EXPANSION JOINT (AT I-74 BRIDGE INTERFACE)	1	LF
N/A	Bridge/ Building	EXCAVATION, CLASS 20	595	CY
N/A	Bridge/ Building	EXCAVATION, CLASS 22	17	CY
N/A	Bridge/ Building (03)	STRUCTURAL CONCRETE	136	CY
N/A	Bridge/ Building (03)	CONCRETE SLAB FIRST FLOOR	504	SF
N/A	Bridge/ Building (03)	CONCRETE TOPPING SECOND FLOOR	504	SF
*	Bridge/ Building (03)	REINFORCING STEEL	13440	LB
*	Bridge/ Building (05)	STRUCTURAL STEEL AND ELEVATOR SUPPORT	69739	LB
X	Bridge/ Building (05)	METAL FLOOR DECK	504	SF
N/A	Building (07)	ROOF INSUL - 5" RIGID - R-25	800	SF
N/A	Building (07)	INSUL - CLG - 6" BATTS - R-20	480	SF
N/A	Building (07)	INSUL - FLOOR - 9 1/2" BATTS - R-30	400	SF
N/A	Building (07)	INSUL - WALL - 3 1/2" BATTS - R-13	2325	SF
N/A	Building (07)	INSUL - WALL - 6" BATTS - R-19	2400	SF
N/A	Building (07)	PERIMETER INSUL - 2" RIGID - R-10	1100	SF
N/A	Building (07)	STANDING SEAM METAL ROOFING	800	SF
N/A	Building (06)	DENS DECK	800	SF
N/A	Building (07)	VAPOR BARRIER	8	SY
N/A	Building (07)	GUTTER ENCLOSURE	26	LF
N/A	Building (07)	COMPOSITE METAL PANELS @ FASCIA	200	SF
X	Building (09)	GYP BD SHAFT WALL ASSEMBLY	300	SF
X	Building (09)	GYP BD PARTITION WALL ASSEMBLY - 3 5/8"	1020	SF
X	Building (09)	GYP BD PARTITION WALL - 6"	1750	SF
N/A	Building (09)	GYP BD CEILING SUSPENSION SYSTEM	570	SF
X	Building (09)	ACOUSTICAL CEILING SUSPENSION ASSEMBLY	300	SF
N/A	Building (09)	PAINT EXPOSED STEEL	1260	SF
N/A	Building (03)	STAINED CONCRETE FLOOR	800	SF
N/A	Building (08)	CURTAIN WALL ASSEMBLY	6400	SF
No	Building (14)	ELEVATORS	2	EA
X	Building (08)	HM DOOR FRAMES - INT	3	EA
X	Building (08)	HM DOORS - INT - W/ HARDWARE	3	EA
X	Building (08)	ALUM DOORS - EXT - W/ HARDWARE	2	EA
N/A	Building (08)	CANOPIES	2	EA
No	Building (23)	2 TON HVAC SYSTEM - GROUND LEVEL	1	LS
No	Building (23)	1.5 TON HVAC SYSTEM - ELEVATOR EQUIPMENT	1	LS
No	Building (23)	2 TON HVAC SYSTEM - BRIDGE LEVEL	1	LS
No	Building (23)	5 TON COOLING SYSTEM - HOISTWAY	1	LS
X	Building (23)	HOISTWAY HEATING - FIN TUBE - 3 KW	5	EA
No	Building (23)	EXHAUST SYSTEM	1	LS
No	Building (22)	FLOOR DRAINS	2	EA
No	Building (22)	TRAP PRIMERS	2	EA
No	Building (22)	CLEAN-OUTS	3	EA
No	Building (22)	ELECTRIC WATER HEATER	1	EA
No	Building (22)	BACKFLOW PREVENTER	1	EA
X	Building (22)	DOWN-SPOUT NOZZLE	2	EA
No	Building (22)	ELEVATOR SUMP PUMP SYSTEM	1	EA
No	Building (22)	CAST-IRON PIPING - 4", INSULATED	170	LF
N/A	Building (22)	COPPER PIPING - 1", INSULATED	100	LF
N/A	Building (22)	MOP SINK	1	EA
No	Building (26)	ELECTRICAL SERVICE	1	LS
No	Building (26)	POWER DISTRIBUTION	1	LS
X	Building (26)	LIGHTING	1	LS
No	Building (26)	SYSTEMS	1	LS
No	Building (22)	HEAT TRACE	1	LS
*	Building (27)	CLOSED CIRCUIT TELEVISION CAMERA	6	EA
*	Building (27)	SECURITY SERVER	1	EA

*	Building (27)	CABINET RACK	1	EA
*	Building (27)	2" CONDUIT, HDPE	100	LF
*	Building (27)	1" CONDUIT, HDPE	200	LF

Notes

- 1 The Unit Cost Rates listed were updated to account for inflation up to 2020
- 2 " * " Assumes the item listed will be sourced thru same vendor/manufacturer used on other I-
- 3 "X" means item is available meeting Buy America requirements. May require Single Source
- 4 "N/A" or not applicable means that either the item listed has no substantial iron/steel content or
- 5 **"No" - Item does not meet "Buy America" requirements and of which these items are applied to the Waiver Request**
- ** Excludes cost estimate information