



REPAIR COST ESTIMATE

K1D683

| | | |
|---|-------------------|--|
| LOCATION OF DAMAGE PROPERTY: SR 018 Begin MP: 27.90 Dir: Westbound under I-90, right side | COUNTY 17 King | DAMAGE CODE 31 Guardrail, Leading End |
|---|-------------------|--|

| | |
|--|--|
| DATE DAMAGE OCCURRED OR OBSERVED: 05/17/2014 OCCURRED | DESCRIPTION OF DAMAGES guardrail, leading end |
|--|--|

| | |
|--|---|
| NAME AND ADDRESS OF OWNER: [REDACTED] | NAME AND ADDRESS OF DRIVER: [REDACTED] |
|--|---|

| | | | | |
|---|------------------------|-------------|--|----------------|
| YEAR, MAKE, TYPE OF VEHICLE: 1995 Mack Tractor | LICENSE: [REDACTED] | DAMAGE TAG: | POLICE DIV: Washington State Patrol | BADGE: 1095 |
|---|------------------------|-------------|--|----------------|

REPAIR COST DISTRIBUTION ESTIMATE

| LABOR DESCRIPTION | QTY | REG. HOURS | O/T HOURS | AMOUNT |
|------------------------------|-----|------------|-----------|-------------------|
| Maintenance Tech. 2 | 3 | 9.0 | | \$1,193.81 |
| Maintenance Tech. 3 | 1 | 9.0 | | \$411.57 |
| Maintenance Trainee | 1 | 9.0 | | \$300.16 |
| TOTAL LABOR ESTIMATE: | | | | \$1,905.54 |

| EQUIPMENT TYPE | QTY | HOURS | AMOUNT |
|--|-----|-------|-----------------|
| 0437 - Truck; 1 Ton; with Dump Body; Regular Cab; Diesel | 1 | 9.0 | \$36.00 |
| 0604 - Truck; Above 38,000 GVW; 4x2; Automatic Transmission; Contractor Body; with front plow | 1 | 9.0 | \$108.10 |
| 0825 - Truck; Flatbed; Guardrail Repair; 54,000 GVW; with Knuckle boom Crane | 1 | 9.0 | \$94.66 |
| 0840 - Truck; Cab & Chassis; 4X2; Multi-Purpose Use | 1 | 9.0 | \$58.85 |
| 1004 - Tilt Trailer; 12,000 Lbs | 1 | 9.0 | \$9.61 |
| 1206 - Backhoe; Excavator; Compact; Track Mounted; 7-8K Operating Weight | 1 | 9.0 | \$29.82 |
| TOTAL EQUIPMENT ESTIMATE: | | | \$337.04 |

| MATERIAL TYPE | QTY | AMOUNT |
|--|-----|-------------------|
| Block, Guard Rail Spacer 6x8x14" | 1 | \$3.72 |
| CRT Breakaway Post | 6 | \$261.12 |
| ET 2000/SRT 350 mud post for 27" rail | 2 | \$85.34 |
| Guard Rail, ET-2000 32G | 1 | \$184.44 |
| Guard Rail, W Beam 12' 6" Straight Section | 6 | \$654.79 |
| TOTAL MATERIAL ESTIMATE: | | \$1,189.41 |



REPAIR COST ESTIMATE

K1D683

| | | |
|---|-------------------|--|
| LOCATION OF DAMAGE PROPERTY: SR 018 Begin MP: 27.90 Dir: Westbound under I-90, right side | COUNTY 17 King | DAMAGE CODE 31 Guardrail, Leading End |
|---|-------------------|--|

| MISCELLANEOUS CHARGES - DESCRIPTION | QTY | AMOUNT |
|--------------------------------------|-----|---------------|
| | | \$0.00 |
| TOTAL MISCELLANEOUS ESTIMATE: | | \$0.00 |

TOTAL CHARGES: \$3,431.98

| | | | |
|--|---------------------|---|-------------------|
| MAINT. AREA LOCATION: Area 5 Bellevue | ORG CODE: 415510 | CONT. SECTION a51018 | JOB NO: K1D683 |
| SUBMITTED BY: Donald Nelson | DATE: 06/09/2014 | | |
| APPROVED BY: Jim McBride | DATE: 06/10/2014 | OFFICE USE ONLY: Estimate Only: Y Accident Rpt: E328825 Revised Estimate: N Work Completed: Y Work Completed Date: 06/05/2014 | |



NO STOPPING OR PARKING



EAST
← Spokane

06/06/2014

← 90 EAST
Spokane

06/06/2014